BRUKS Siwertell
BULK HANDLING & WOOD PROCESSING



SIWERTELL SHIP UNLOADER - TAIWAN

CLEAN CEMENT OPERATION IN TAIWAN

This Siwertell continuous screw-type ship unloader was supplied to Chia Hsin Cement Corp for handling cement, and was followed by an order of a horisontal screw conveyor installed along the jetty to receive the unloaded cement.

About

The rail-mounted 800t/h unloader was delivered as part of a new facility for cement unloading, storage and bulk loading in the port of Keelung.

The contract signed for the unloader was followed by an order for a horizontal screw conveyor, installed along the jetty to receive the unloaded cement at 800t/h.

A belt lifter arrangement is included in the delivery for a smooth and totally enclosed transfer of cement between the unloader and the jetty conveyor.

FACTS

CATEGORIES:

- **Ship Unloading**

MATERIALS:

- **Cement**

CUSTOMER:

Chia Hsin Cement Corp

ADDITIONAL FACTS:

Unloader model	ST 490-F, rail-mounted
Unloading capacity	800t/h
Maximum ship size	40,000 dwt
Total weight	262t
Jetty conveyor length	HNL 800, length 170m

PRODUCTS:

- Ship unloading

LOCATION:

Port of Keelung, Taiwan

FOR MORE INFORMATION, PLEASE CONTACT US

Regional Sales Manager, East Asia
Ola Jeppsson
+46 709741183
ola.jeppsson@bruks-siwertell.com

SCAN THE QR-CODE:
View the Case online